
City of Federal Way Public Works Department 2022 STORM PIPE REPAIR July 2022 RFB NUMBER 22-008

		DRAWING INDEX
SHEET	DRAWING	DESCRIPTION
1	COVER	COVER SHEET
2	NOTES	GENERAL NOTES
3	DETAILS	DETAILS
		SCHEDULE A - BASE BID
4	A1	SITE PLAN: 2707 SW 322ND ST
5	A2	SITE PLAN: 33005 35TH AVE SW
6	A3	SITE PLAN: 33406 22ND AVE SW
7	A4	SITE PLAN: 3103 SW 339TH ST
8	A5	SITE PLAN: 2648 SW 349TH PL
9	A6	SITE PLAN: 36432 10TH CT SW
		SCHEDULE B - ALTERNATE 1
10	B1	SITE PLAN: SW 316TH PL & 11TH PL SW
11	B2	SITE PLAN: 4TH AVE S & S 318TH PL
12	B3	SITE PLAN: 8TH AVE S & S 317TH ST
13	B4	SITE PLAN: 1ST PL S & S 316TH PL
14	B5	SITE PLAN: 31120 5TH WAY S
		SCHEDULE C - ALTERNATE 2
15	C1	SITE PLAN: 39TH AVE SW & 39TH PL SW
16	C2	SITE PLAN: 12TH AVE SW & MARINE VIEW DR SW
17	C3	SITE PLAN: S 302ND ST NEAR 5TH AVE S
18	C4	SITE PLAN: REDONDO WAY S NEAR 13TH AVE S
19	C5	SITE PLAN: 2403 S 298TH ST
		TRAFFIC CONTROL
20	TC-1	TRAFFIC CONTROL PLAN 1
21	TC-2	TRAFFIC CONTROL PLAN 2
22	TC-3	TRAFFIC CONTROL PLAN 3





215TINE J. MUL		DRAWI	NG VERSION / REVISION LOG	
	NO.	DATE	REVISION	2022 STORM
A TON				
Roman Strength Streng				COVER
SJONAL ENGI				
24-'Jun-2022				

R SHEET

M PIPE REPAIR

COVER 1 OF 23

CITY PROJECT 34288

SHEET

DATE

100% DRAWINGS

DESIREE S. WINKLER P.E DEPUTY PUBLIC WORKS DIRECTOR

6-24-22

APPROVED FOR CONSTRUCTION


ESC NOTES

- ESC MEASURES MUST BE INSTALLED AND PROPERLY FUNCTIONING PRIOR TO OR IN CONJUNCTION WITH ALL EXCAVATION SO AS TO ENSURE THAT TRANSPORT OF SEDIMENT TO SURFACE WATERS, DRAINAGE SYSTEMS, AND ADJACENT PROPERTIES IS MINIMIZED.
- ESC MEASURES SHOWN ON THIS PLAN, IF ANY, ARE THE MINIMUM 2. REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING CONSTRUCTION, THESE ESC MEASURES SHALL BE UPGRADED AS NEEDED AT NO ADDITIONAL COST TO THE CITY FOR UNEXPECTED STORM EVENTS AND MODIFIED TO ACCOUNT FOR CONTRACTOR'S MEANS AND METHODS OF CONSTRUCTION.
- ESC FACILITIES SHALL BE INSPECTED DAILY BY CONTRACTOR'S ESC 3. SUPERVISOR AND MAINTAINED TO ENSURE CONTINUED PROPER FUNCTIONING.
- ANY AREAS OF EXPOSED SOILS, INCLUDING ROADWAY EMBANKMENTS, THAT WILL NOT BE DISTURBED FOR TWO CONSECUTIVE DAYS DURING WET SEASON OR SEVEN DAYS DURING DRY SEASON SHALL BE IMMEDIATELY STABILIZED WITH APPROVED ESC METHODS.
- ANY AREA NEEDING ESC MEASURES THAT DO NOT REQUIRE IMMEDIATE 5. ATTENTION SHALL BE ADDRESSED WITHIN SEVEN (7) DAYS.
- AT NO TIME SHALL MORE THAN ONE (1) FOOT OF SEDIMENT BE ALLOWED TO 6. ACCUMULATE WITHIN A CATCH BASIN. ALL CATCHBASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. CLEANING OPERATION SHALL NOT FLUSH SEDIMENT-LADEN WATER INTO DOWNSTREAM SYSTEM.
- PRIOR TO BEGINNING OF WET SEASON (OCT. 1), ALL DISTURBED AREAS SHALL 7. BE REVIEWED TO IDENTIFY WHICH ONES CAN BE SEEDED IN PREPARATION FOR WINTER RAINS. DISTURBED AREAS SHALL BE SEEDED WITHIN ONE WEEK OF BEGINNING OF WET SEASON. A SKETCH MAP OF THOSE AREAS TO BE SEEDED AND THOSE AREAS TO REMAIN UNCOVERED SHALL BE SUBMITTED TO ENGINEER.
- INSTALL INLET PROTECTION PER WSDOT STANDARD PLAN I-40.20-00 ON ALL 8. STORM DRAIN INLETS NEAR CONSTRUCTION SITE THAT MAY CATCH RUNOFF FROM CONSTRUCTION SITE.
- PLUG STORM DRAIN PIPE DOWNSTREAM OF CONSTRUCTION SITE. DIRECT SURFACE RUNOFF AWAY FROM CONSTRUCTION SITE.
- 10. SCHEDULE C HAVE OUTFALLS IN CLOSE PROXIMITY TO REPAIR.
- 11. UPSTREAM STRUCTURE WILL BE PLUGGED AND HAVE DEWATERING SYTEMS ON SITE AT ALL TIMES THAT IS CAPABLE OF DIVERTING STORMWATER AROUND CONSTRUCTION ZONE.
- 12. ONCE REPAIR HAS BEEN MADE, THE DOWNSTREAM STRUCTURE SHALL BE PLUGGED AND THE PIPE SHALL BE CLEARED OF ANY DEBRIS AND SEDIMENT THAT ACCUMULATED DURING CONSTRUCTION.

		STORM PIPE TO BE REPAIRED	
—— OH——	DH	OVERHEAD LINES	w w w
D	—SD	STORM PIPE	
i — —	— G — —	GAS MAIN	C
′R	—PWR—	BURIED ELECTRICAL	3
M	—-СОМ	BURIED COMMUNICATION CABLE	CB
	\square	FLOW DIRECTION	
	OF	OUT FALL	

LEGEND





DRAFTED:	J. COLE	
DESIGNED:	J. COLE	
REVIEWED: (C. MULLEN	
APPROVED: I	D. WINKLER	

ABBREVIATIONS

ACP	ASPHALT CONCRETE PAVEMENT
AC	ASBESTOS CONCRETE
CB	CATCH BASIN
COFW	CITY OF FEDERAL WAY
CONC	CONCRETE
CMP	CORRUGATED METAL PIPE
CP	CONCRETE PIPE
CSTC	CRUSHED SURFACE TOP COURSE
DIA	DIAMETER
ESC	EROSION SEDIMENTATION CONTROL
EXIST.	EXISTING
G	UNDERGROUND GAS
HDPE	HIGH DENSITY POLY ETHYLENE
HMA	HOT MIX ASPHALT
NTS	NOT TO SCALE
OH	OVERHEAD LINE
PWR	UNDERGROUND POWER
SD	STORM DRAIN
SS	SANITARY SEWER
TEL	UNDERGROUND TELEPHONE
W	WATER

- 3
- 4
- 5. PER COFW STANDARD 3-28.
- CONDITIONS.
- 8.


- CITIES DIRECTION.

 WATER MAIN
 ROW/PL LINES
SANITARY MANHOLE
EXISTING STORM CATCH BASIN

SANITARY SEWER PIPE

END OF PIPE

CB INLET PROTECTION






OUTLET PROTECTION

CLEAR AND GRUB

CONCRETE

ASPHALT

EASEMENT



2022 STORM PIPE REPAIR GENERAL NOTES AND LEGEND

GENERAL NOTES

1. UNLESS OTHERWISE NOTED ON THE PLAN, CONTRACTOR SHALL REBUILD, REPAIR, RESTORE, AND MAKE GOOD ALL DAMAGES AND DISTURBANCES TO ANY AND ALL IMPROVEMENTS THAT EXIST PRIOR TO THE CONSTRUCTION TO THEIR ORIGINAL CONDITIONS. THE EXTENT OF SURFACE DISTURBANCE MAY VARY DEPENDING ON CONTACTOR'S CHOSEN CONSTRUCTION METHOD. BIDDERS ARE ENCOURAGED TO INSPECT THE SITE CONDITIONS BEFORE SUBMITTING BIDS.

2. SEEDING IS NOT AN ALLOWED METHOD FOR RESTORING DISTURBED LAWN. CONTRACTOR SHALL EITHER INSTALL NEW SOD, OR REMOVE, PRESERVE AND REUSE EXISTING SOD TO RESTORE DISTURBED LAWN. ENGINEER'S REVIEW AND APPROVAL OF THE CONDITIONS OF PRESERVED SOD IS REQUIRED PRIOR TO REUSING EXISTING SOD. IF PRESERVED SOD IS NOT APPROVED, NEW SOD SHALL BE USED.

TRENCH OPEN AREA MUST BE COVERED WITH COLD MIX ASPHALT TEMPORARY PAVEMENT NO LATER THAN NEXT CALENDAR DAY AFTER TRENCH BACKFILL IS COMPLETE AND BEFORE OPEN TO TRAFFIC. WHICHEVER COMES FIRST. COLD MIX SHALL BE PLACED IN A 2-INCH MINIMUM THICKNESS. MAINTAIN AND/OR REPLACE COLD MIX AS NECESSARY AT ENGINEER'S DISCRETION.

THE CONTRACTOR MAY TEMPORARILY RESTORE SITES WITH COLD MIX ASPHALT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT TEMPORARY PAVEMENT IS PROPERLY MAINTAINED. PERMANENT PAVEMENT RESTORATION MAY BE COMPLETED FOR AN ENTIRE SCHEDULE AT ONCE, RATHER THAN AS EACH INDIVIDUAL SITE IS COMPLETED AS LONG AS TEMPORARY RESTORATION IS PROPERLY MAINTAINED AND THERE ARE NO OTHER ISSUES.

BACKFILL COMPACTION AND PLACEMENT WILL BE PERFORMED IN COMPLIANCE WITH WSDOT STANDARD SPECIFICATIONS. ALL PERPENDICULAR CROSSINGS OF THE ROADWAY WILL BE BACKFILLED 100% WITH CSBC. THE ASPHALT SECTION SHALL BE RESTORED WITH A MINIMUM OF THREE (3") INCHES OF ASPHALT, HMA ¹/₂". OR BE REPLACED TO THE ORIGINAL CONDITION IF THICKER. AT THE CITY'S SOLE DISCRETION.

6. AERIAL PHOTOGRAPHS WERE TAKEN IN 2015. CURRENT CONDITIONS MAY DIFFER. PROPERTY AND RIGHT-OF-WAY LINES ARE APPROXIMATE AND ARE SHOWN FOR REFERENCE ONLY.

7. CONTRACTOR SHALL INVESTIGATE PROJECT SITE AND BID THE PROJECT BASED ON CURRENT SITE

PIPE LOCATION, LENGTH, DEPTH AND DIAMETER ARE APPROXIMATE ESTIMATE ONLY. CONTRACTOR SHALL FIELD VERIFY THE INFORMATION PRIOR TO WORK.

9. PIPE MATERIAL TYPE CHANGE COULD OCCUR WITHIN SOME PIPES AS A RESULT OF REPLACING FAILED PIPE SEGMENTS IN THE PAST. CONTRACTOR TO VERIFY.

10. GROUNDWATER BASE FLOW WILL LIKELY EXIST IN SOME PIPES DURING CONSTRUCTION. CONTRACTOR SHALL TAKE NECESSARY MEASURES TO BYPASS BASE FLOW PRIOR TO WORK.

11. DEWATERING SYSTEMS. PROVIDED BY THE CONTRACTOR SHALL BE ONSITE AND AVAILABLE.

12. ACCESS TO SOME PIPES CAN BE DIFFICULT. CONTRACTOR SHALL BID THE PROJECT AFTER CAREFULLY EXAMINING THE EXISTING CONDITIONS.

13. NOT ALL EXISTING UTILITIES ARE SHOWN ON PLAN. CONTRACTOR SHALL INSPECT SITE AND CONTACT UTILITY OWNERS/OPERATORS TO DETERMINE UTILITY LOCATIONS WHERE NECESSARY.

14. THE CONTRACTOR SHALL CLEAN AND CAMERA THE REPAIRED PIPE TO ENSURE REPAIR WAS COMPLETED CORRECTLY AND THERE IS NOT DEBRIS OR SEDIMENT PRESENT.

15. UPSTREAM STRUCTURE WILL BE PLUGGED AND HAVE DEWATERING SYTEMS ON SITE AT ALL TIMES THAT IS CAPABLE OF DIVERTING STORMWATER AROUND CONSTRUCTION ZONE.

16. ONCE REPAIR HAS BEEN MADE, THE DOWNSTREAM STRUCTURE SHALL BE PLUGGED AND THE PIPE SHALL BE CLEARED OF ANY DEBRIS AND SEDIMENT THAT ACCUMULATED DURING CONSTRUCTION.

17. CONTRACTOR SHALL CONFIRM INSTALLED LENGTH OF PIPE WITH CITY OF FEDERAL WAY INSPECTOR ONSITE PRIOR TO FINAL BACKFILL OF TRENCH.

18. CONTRACTOR SHALL ENSURE MAIL AND REFUSE SERVICE IS NOT INTERRUPTED DURING CONSTRUCTION AND SHALL COORDINATE WITH SERVICE PROVIDER ON DELIVERY/PICKUP TIME.


19. IF CONTRACTOR IS UNABLE TO COMPLETE THE PERMANENT PIPE REPAIR WITHIN THE ALLOWABLE WORKING HOURS AND WEATHER IS EXPECTED, THE CONTRACTOR SHALL INSTALL TEMPORARY PIPE AND PIPE CONNECTIONS IN ALL OPEN EXCAVATION INCLUDING DITCHES, TRENCHES, SWALES, HOLES PER THE

100% DRAWINGS

34288 SHEET

CITY PROJECT #

NOTES




CEMENT CONCRETE ROLLED CURB AND GUTTER






	DRAFTED: J. COLE	and the second		DRAWI	NG VERSION / REVISION LOG	
		RISTINE J. MUL	NO.	DATE	REVISION	2022 STORN
	DESIGNED: J. COLE	TO AN AND AND AND AND AND AND AND AND AND				
	REVIEWED: C. MULLEN	Par Aregisteren State				DE
ig.	APPROVED: D. WINKLER	24-Jun-2022				



OUTFALL DETAIL

	100% DRAWINGS
M PIPE REPAIR	CITY PROJECT #: 34288
TAILS	
	3 OF 23



مععم.		DRAWI	NG VERSION / REVISION LOG		
NINE J. MUL	NO.	DATE	REVISION	2022 STORM PIPE	
				SITE PLAN: 2707 SW 3	
REGISTERED BIONAL ENGINE				(PIPE #3251)	
24-' tur-2022					


REMOVE EXISTING DAMAGED CONCRETE PIPE, AND REPLACE WITH DUCTILE IRON STORM SEWER PIPE, 12 IN. DIA.
 HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER COFW DWG. NO. 3-28



10 CONNECT TO EXISTING PIPE WITH FERNCO COUPLER OR APPROVED EQUIVALENT


GENERAL NOTES

REPLACE CURB & GUTTER FROM JOINT TO JOINT.
 BACKFILL TRENCHES WITH CSTC.



M PIPE REPAIR 707 SW 322ND ST

A1




ALSTINE J. MULT		DRAWI	NG VERSION / REVISION LOG	
	NO.	DATE	REVISION	2022 STORM PIPE
TO CALLER AND A REAL				SITE PLAN: 33005 35TH
BOR ALGISTERED LE				(PIPE #2307)
24-Jun-2022				$(I II \square \pi 2307)$

 REMOVE EXISTING DAMAGED CONC. PIPE, AND REPLACE WITH HIGH-DENSITY POLYETHYLENE (HDPE) PIPE, 15 IN. DIA.
 HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER COFW DWG. NO. 3-28 0 CONNECT TO EXISTING PIPE WITH FERNCO COUPLER


GENERAL NOTES

REPLACE CURB & GUTTER FROM JOINT TO JOINT.
 BACKFILL TRENCHES WITH CSTC.



M PIPE REPAIR 3005 35TH AVE SW

A2



and the second	D	RAWI	NG VERSION / REVISION LOG	
STINE J. MUL	NO.	DATE	REVISION	2022 STORM
A Pure Control				
39804 REGISTERED				SITE PLAN: 334
SUDNAL END				(PIPE
24-jun-2022				(

SW 339TH ST I.E=2' (BELOW RIM) 8" CONCRETE PIPE (4) $\overline{(7)}$ (10) START 170+12 3103 SW 339th St Federal Way WA 98023 ω **__** ST AVE SW


UTILITIES AS SHOWN ARE APPROXIMATE.





\mathbf{m}	DRAFTED: J. COLE	
	DESIGNED: J. COLE	
	REVIEWED: C. MULLEN	
Know what's below. Call before you dig.	APPROVED: D. WINKLER	





		DRAWI	NG VERSION / REVISION LOG		
STINE J. MULT OF WASHINGTON				2022 STORM PIPE	
				SITE PLAN: 3103 SW	
24-Jun-2022				(PIPE #1192)	

M PIPE REPAIR 103 SW 339TH ST

34288

7 OF 23

SHEET A4

CITY PROJECT #


100% DRAWINGS

GENERAL NOTES

* TRENCH BACKFILL SHALL BE CSTC.

CONSTRUCTION NOTES REMOVE EXISTING DAMAGED CONCRETE PIPE, AND REPLACE WITH DUCTILE IRON STORM SEWER PIPE, 8 IN. DIA.
 HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER COFW DWG. NO. 3-28 10 CONNECT TO EXISTING PIPE WITH FERNCO COUPLER OR APPROVED EQUIVALENT

GRAPHIC SCALE



gineering division\PROJECTS\ACTIVE\34288 - 2022 storm repair phase 4\03 PE\ACAD\288_2021_Sch A-E Plus.dwg, 6/2

DRAWING VERSION / REVISIO	
RISTINE J. MULLEN NO. DATE REVISION	2022 STORM
The system of th	SITE PLAN: 26
24 - Jun - 2022	(PIPE



0	Q	5	10	20

CONSTRUCTION NOTES(5)REMOVE EXISTING DAMAGED CMP PIPE, AND REPLACE
WITH HIGH-DENSITY POLYETHYLENE (HDPE) PIPE, 15
IN. DIA.(7)HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER
COFW DWG. NO. 3-28(10)CONNECT TO EXISTING PIPE WITH FERNCO COUPLER
OR APPROVED EQUIVALENT(21)CEMENT CONCRETE SIDEWALK PER COFW DETAIL
3-03 AND 3-12(22)CEMENT CONCRETE ROLLED CURB AND GUTTER
PER DETAIL SHEET 03


100% DRAWINGS

M PIPE REPAIR

648 SW 349TH PL PE #9601) CITY PROJECT #

SHEET

A5



UTILITIES AS SHOWN ARE APPROXIMATE.






$\overline{\mathbf{m}}$	DRAFTED: J. COLE	
	DESIGNED: J. COLE	
	REVIEWED: C. MULLEN	
Know what's below. Call before you dig.	APPROVED: D. WINKLER	



and the second		DRAWI	NG VERSION / REVISION LOG			
REAL STINE J. MULTER REAL STINE J. MULTER ALSOF WASHINGTON STANDARD STREET	NO.	DATE	REVISION	2022 STORM		
				SITE PLAN: 36		
24-Jun-2022				(PIPE		



CONSTRUCTION NOTES

REMOVE EXISTING DAMAGED HDPE PIPE AND REPLACE WITH HIGH-DENSITY POLYETHYLENE (HDPE) PIPE, 12 IN. DIA. HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER COFW DWG. NO. 3-28 10 CONNECT TO EXISTING PIPE WITH FERNCO COUPLER OR APPROVED EQUIVALENT (11) CEMENT CONC. TRAFFIC CURB AND GUTTER PER COFW DWG. NO. 3-4 (12) CEMENT CONC. DRIVEWAY ENTRANCE TYPE RESIDENTIAL PER COFW DWG. NO. 3-6

GENERAL NOTES

- JOINT TO JOINT REPLACEMENT ON CURB GUTTER AND SIDEWALK IS REQUIRED. * TRENCH BACKFILL SHALL BE CSTC.

100% DRAWINGS


M PIPE REPAIR

6432 10TH CT SW E #16475)

CITY PROJECT #

34288


SHEET A6









	DRAFTED:	J. COLE	
	DESIGNED:	J. COLE	
	REVIEWED:	C. MULLEN	3
E.	APPROVED:	D. WINKLER	











 REMOVE EXISTING DAMAGED CONCRETE PIPE, AND
 REPLACE WITH HIGH-DENSITY POLYETHYLENE (HDPE) PIPE, 8 IN. DIA.
 HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER COFW DWG. NO. 3-28 (17) CONNECTION TO DRAINAGE STRUCTURE

GENERAL NOTES

* TRENCH BACKFILL SHALL BE CSTC.


100% DRAWINGS 2022 STORM PIPE REPAIR

(PIPE #16109)

CITY PROJECT # 34288

SHEET

B1









E	DRAFTED:
	DESIGNED:
LEN	REVIEWED:
KLER	APPROVED:



STINE J. MULLER OF WASHINGTON 39804 ALCOISTERED		DRAWI	NG VERSION / REVISION LOG		
	NO.	DATE	REVISION	2022 STORM PIPE	
				SITE PLAN: 4TH AVE S 8	
SSYONAL ENGI				(PIPE #8132)	
24-'Jun-2022					








100% DRAWINGS

M PIPE REPAIR AVE S & S 318TH PL CITY PROJECT # 34288

SHEET

B2




UTILITIES AS SHOWN ARE APPROXIMATE.







$\overline{\mathbf{m}}$	DRAFTED: J. COLE	
	DESIGNED: J. COLE	
	REVIEWED: C. MULLEN	3
Know what's below. Call before you dig.	APPROVED: D. WINKLER	



(BEL CRE CB	RIM) PE	
24	210	
- All and a second		

-	DRAWI	NG VERSION / REVISION LOG		
ALSTINE J. MULLEN	O. DATE	REVISION	2022 STORN	
			SITE PLAN: 8TH A	
24-Jun-2022			(PIPES #7922,	





GENERAL NOTES

* TRENCH BACKFILL SHALL BE CSTC.

100% DRAWINGS

M PIPE REPAIR


AVE S & S 317TH ST 2, #8833 & #8836)

CITY PROJECT #

34288

SHEET


B3









DRAFTED:	J. COLE	
DESIGNED:	J. COLE	
REVIEWED:	C. MULLEN	
APPROVED:	D. WINKLER	







GENERAL NOTES

* TRENCH BACKFILL SHALL BE CSTC.

100% DRAWINGS


2022 STORM PIPE REPAIR

CITY PROJECT # 34288

SHEET

B4

(PIPE #692)



*** ALL UTILITIES ARE APPROXIMATE. CONTRACTOR RESPONSIBLE FOR LOCATING.***






J. COLE	DRAFTED:
J. COLE	DESIGNED:
C. MULLEN	REVIEWED:
D. WINKLER	APPROVED:



EASEMENT

	DRAWING VERSION / REVISION LC	
ASTINE J. MUI ASTINE J. MUI ASTINE J. MUI ASTINE	NO. DATE REVISION	2022 STORM
The system of th		SITE PLAN: 3
24-Jun-2022		(PIPE




GENERAL NOTES

 * TRENCH BACKFILL SHALL BE CSTC
 * BYPASS AND PUMPING PLAN REQUIRED ON ALL SCHEDULES.

100% DRAWINGS

CITY PROJECT #


M PIPE REPAIR 34288 31120 5TH WAY S SHEET E #16582) 14 OF 23







	DRAFTED:	J. COLE
	DESIGNED:	J. COLE
	REVIEWED:	C. MULLEN
į.	APPROVED:	D. WINKLER



and the second	DRAWING VERSION / REVISION LOG	
BISTINE J. MU.	NO. DATE REVISION	2022 STORM
LO L		
ROF REGISTERED TH		SITE PLAN: 39TH A
SIGNAL ENGI		(PIPF
24-'jun-2022		- · · · · -

100% DRAWINGS

M PIPE REPAIR


AVE SW & 39TH PL SW PE #1804)

CITY PROJECT #

34288

SHEET

C1








	DRAFTED: J. COLE	A REAL PROPERTY OF THE PROPERT	DRAWING VERSION / REVISION LOG	2022 STORM
	DESIGNED: J. COLE	ALSTINE J. MULT	NO. DATE REVISION	
	REVIEWED: C. MULLEN			SITE PLAN: 12TH AVE S
1	APPROVED: D. WINKLER	STONAL ENGIN		(PIPE
	AFFROVED. D. WINKLER	24- jun-2022		(





GENERAL NOTES

- JOINT TO JOINT REPLACEMENT ON SIDEWALK IS
- REQUIRED. * TRENCH BACKFILL SHALL BE CSTC.

100% DRAWINGS

M PIPE REPAIR

SW & MARINE VIEW DR SW

E #11824)


16 OF 23

CITY PROJECT #

34288


SHEET


C2



DRAWING VERSION / REVISION LOG	
NO. DATE REVISION	2022 STORM
PROPERTIE REDUCTION	SITE PLAN: S 302NE
24-Jun-2022	(PIPE







GENERAL NOTES

* TRENCH BACKFILL SHALL BE CSTC.

100% DRAWINGS

M PIPE REPAIR


ID ST NEAR 5TH AVE S PE #9221)


CITY PROJECT #

34288

SHEET

C3





	DRA	WING VERSION / REVISION LOG	
21STINE J. MUL	NO. DAT	E REVISION	2022 STORM
EX ALL AND ALL			
ROR 39804 REGISTERED			SITE PLAN: REDONDO
74-740-2022			(PIPE
21 1000 2022			



GRAPHIC SCALE

6 REMOVE EXISTING DAMAGED CMP PIPE, AND REPLACE WITH HIGH-DENSITY POLYETHYLENE (HDPE) PIPE, 36 IN. 0 CONNECT TO EXISTING PIPE WITH FERNCO COUPLER OR APPROVED EQUIVALENT (19) SHOULDER RESTORATION

GENERAL NOTES

- TRENCH BACKFILL SHALL BE CSTC. *
- ALL WORK IS IN SOFT SURFACE SHOULDER. * * UPSTREAM STRUCTURE AT STA 30+00 IS VERY OLD
- BRICK STACKED. DAMAGE TO STRUCTURE WILL BE AT CONTRACTORS EXPENSE.

100% DRAWINGS

M PIPE REPAIR

WAY S NEAR 13TH AVE S

E #24855)


18 OF 23

CITY PROJECT #

34288

SHEET

C4



*** ALL UTILITIES ARE APPROXIMATE. CONTRACTOR RESPONSIBLE FOR LOCATING.***





Dł	RAFTED:	J. COLE	
DE	SIGNED:	J. COLE	
RE	VIEWED:	C. MULLEN	đ
APF	ROVED:	D. WINKLER	

معققوه.		DRAWI	NG VERSION / REVISION LOG	
RISTINE J. MU.	NO.	DATE	REVISION	2022 STORM
S LAN AGE ON				
ROR 239804 REGISTERED				SITE PLAN: 24
74- Jun - 2022				- (PIPE
21 1040 2022				<u> </u>



GRAPHIC SCALE

CONSTRUCTION NOTES

 REMOVE EXISTING DAMAGED CMP PIPE AND REPLACE WITH HIGH-DENSITY POLYETHYLENE (HDPE) PIPE, 12 IN. DIA. HMA FOR PAVEMENT REPAIR CL. 1/2", PG 58H -22 PER COFW DWG. NO. 3-28
0 CONNECT TO EXISTING PIPE WITH FERNCO COUPLER
21 CEMENT CONCRETE SIDEWALK PER COFW DETAIL 3-03 AND 3-12
22 CEMENT CONCRETE ROLLED CURB AND GUTTER PER DETAIL SHEET 03

GENERAL NOTES

- * JOINT TO JOINT REPLACEMENT ON CURB GUTTER AND SIDEWALK IS REQUIRED.
 * TRENCH BACKFILL SHALL BE CSTC.

100% DRAWINGS

M PIPE REPAIR


2403 S 298TH ST 'E #4283)

CITY PROJECT # 34288


SHEET

C5


19 of 23




L/2 TAPER WORK AREA •• R ROAD LEFT LANE AND CENTER TURN LANE WORK AHEAÇ CLOSURE – 5 LANE ROADWAY W20-NOT TO SCALE W4-2R EFT LANS CLOSED AHEAD W20-5L




	/ING VERSION / REVISION LOG	DRAWI		معققي
2022 STORM	REVISION	DATE	NO.	ALSTINE J. MU.
				ETON ACTON
TRAFFIC CO			' <u> </u>	PROF REGISTERED LE
				ESSIONAL ENGLY
			2	24-'Jun-2022





HALF ROAD CLOSURE – 4 LANE ROADWAY

NOT TO SCALE



	MINI		ANF (IRF TA	PFR I	FNGT		(feet`)				BUF	FER [) Α Τ Α (
	MINIMUM LANE CLOSURE TAPER LENGTH = L (feet) Posted Speed (mph)												NGITL	DINAL			SPACE	E = E)		
WIDTH (feet)	25	30	35	40	45	50	55	60	65	70	SPEED (MPH)	25	30	35	40	45	50	55	60	65	70
10	105	150	205	270	450	500	550		_	_					705	7.0.0					770
11	115	165	225	295	495	550	605	660	_	_	LENGTH (feet)	155	200	250	305	360	425	495	570	645	730
12	125	180	245	320	540	600	660	720	780	840	TRANSPO	ORTABL	E AT	FENU	TOR	ROLL	AHEA	D DIS	TANC	E = R	
	MIN	IIMUM	SHOU	LDER	TAPER	R LENG	GTH =	L/3 (feet)		HOST VEH 9,900 TC	ICLE WEI 22,000 lb					HOST V	EHICLE 22,000		ΗT	
SHOULDER	Posted Speed (mph)								< 45 MPH 45	55 MPH	>	55 MPH	<	45 MPH	4 4	45-55 M	PH	> 55 N	1PH		
WIDTH (feet)	25	30	35	40	45	50	55	60	65	70	100'	123' 172'		172'	74'			100'		150'	
8'	40	40	60	90	120	130	150	160	170	190							<u> </u>				
10'	40	60	90	90	150	170	190	200	220	240		PROTE				WOR	VEH	ICLE)	= K		
	1	1	1	1			1	I	<u> </u>					ECIFIED				-			

CHANNELIZATION DEVICE SPACING (feet)								
MPH TAPER TANGENT								
50	40	80						
35/45	30	60						
25/30	20	40						

NOTES

- 1. SEE SPECIAL PROVISIONS FOR WORK HOUR RESTRICTIONS.
- 2. EXTEND DEVICE TAPER AT L/3 ACROSS SHOULDER.
- 3. DEVICES SHALL NOT ENCROACH INTO THE ADJACENT LANE.
- 4. USE TRANSVERSE DEVICES IN CLOSED LANE EVERY 1000' (FT) (RECOMMENDED).
- 5. DEVICE SPACING FOR THE DOWNSTREAM TAPER SHALL BE 20' (FT).
- 6. ALL SIGNS ARE BLACK ON ORANGE.



Sentered on Opportunity \mathbf{i} DRAFTED: J. COLE DESIGNED: J. COLE REVIEWED: C. MULLEN 33325 8TH AVE S FEDERAL WAY, WA 98003 Know what's below. PHONE: (253) 835-2700 WWW.CITYOFFEDERALWAY.COM Call before you dig. APPROVED: D. WINKLER

EMPORARY	SIGN I	OCATION

- CHANNELIZING DEVICES
- SEQUENTIAL ARROW SIGN
- PROTECTIVE VEHICLE
- PORTABLE CHANGEABLE MESSAGE SIGN
- TEMPORARY SIGN LOCATION (5' MOUNTING HEIGHT)

	DRAWING VERSION / REVISION LOG	DR/
2022 STORM	NO. DATE REVISION	RESTINE J. MULTINO. DA
		S KELS
TRAFFIC CO		Roman Aregister REP AND
		CIDIONAL ENGLY
		24-'fun-2022

	PCMS #1			PCM	S #2				
	1 2			1	2				
	RIGHT / LEFT 1 MILE LANE AHEAD CLOSURE			CENTER LANE CLOSED	NNO LEFT TURNING				
	2.0 SEC	2.0 SEC		2.0 SEC	2.0 SEC				
	FIELD LOCATE OF TEMPOF	E IN ADVANCE RARY SIGNS.		FIELD LOCAT	e in advance Rary signs.				
	SI	IGN SPACI	ING	= X (1)					
RURAL RC	DADS			45 / 55 M	PH 500 [°]	* +/-			
RURAL RC)ADS & URB	AN ARTERIA	\LS	35 / 40 M	PH 350 ²	`+/-			
	ADS & URBAN AL & BUSINES			25 / 30 M	PH 200 [°]	' +/- (2)			
URBAN ST	TREETS			25 MPH OR	LESS 100'	+/- (2)			
 (1) ALL SPACING MAY BE ADJUSTED TO ACCOMMODATE INTERCHANGE RAMPS, AT-GRADE INTERSECTIONS AND DRIVEWAYS. (2) THIS SPACING MAY BE REDUCED IN URBAN AREAS TO FIT ROADWAY CONDITIONS. 									

M PIPE REPAIR

ONTROL PLAN 2


21 OF 23

CITY PROJECT #

34288

SHEET

TC-2



Know what's below.

Call before you dig.

PHONE: (253) 835-2700

WWW.CITYOFFEDERALWAY.COM

APPROVED: D. WINKLER

and a second




TEMPORARY SIGN LOCATION (5' MOUNTING HEIGHT)

LEGEND FLAGGING STATION TEMPORARY SIGN LOCATION И CHANNELIZING DEVICES \bigcirc \square SEQUENTIAL ARROW SIGN PROTECTIVE VEHICLE - RECOMMENDED 6

INTERSECTION LANE CLOSURE – FIVE LANE ROADWAY

- 4. ALL SIGNS ARE BLACK ON ORANGE.
- 3. MAINTAIN A MINIMUM OF ONE ACCESS POINT FOR EACH BUSINESS WITHIN WORK AREA LIMITS.
- 2. IF A SIGNAL IS PRESENT, IT SHALL BE SET TO "RED FLASH MODE" OR TURNED OFF DURING FLAGGING OPERATIONS.
- 1. RECOMMEND EXTENDING DEVICE TAPER (L/3) ACROSS SHOULDER.



TRAFFIC CONTROL PLAN 3

22 OF 23

TC-3

SHEET


34288

CITY PROJECT #

100% DRAWINGS

BUFFER DATA											
Longitudinal buffer space = b											
SPEED (MPH) 25 3				35 40		45	50	55	60	65	70
LENGTH (feet) 155 2		200	250 305		360	425	495	570	645	730	
TRANSPORTABLE ATTENUATOR ROLL AHEAD DISTANCE = R											
		EHICLE TO 22,(/EHICLE 22,000		ΗT	
< 45 MPH	45-	55 MPF	1	> 55 MF	РΗ	< 45 M	PH	45-55	MPH	> 55	MPH
100'		123'		172'		74'		10	00'	1	50'
PROTECTIVE VEHICLE (WORK VEHICLE) = R											
NO SPECIFIED DISTANCE REQUIRED											

OPTIONAL IF 40 MPH OR LESS



SIGN SPACIN	G = X (1)							
RURAL HIGHWAYS	60/65 MPH	800' +/-						
RURAL ROADS	45/55 MPH	500' +/-						
RURAL ROADS & URBAN ARTERIALS	35/40 MPH	350' +/-						
RURAL ROADS & URBAN ARTERIALS	25/30 MPH	200' +/- (2)						
RESIDENTAL & BUSINESS DISTRICTS								
URBAN STREETS 25	MPH OR LESS	100' +/- (2)						
(1) ALL SPACING MAY BE ADJUSTED TO A	ACCOMMODATE IN	TERCHANGE						
RAMPS, AT-GRADE INTERSECTIONS AND DRIVEWAYS.								
(2) THIS SPACING MAY BE REDUCED IN U	IRBAN AREAS TO F	TIT						
ROADWAY CONDITIONS.								

	W20-	BE PREPARED TO STOP 48" 48" -7A	8") 8"		ENTER LA CLOSEI AHEAD 48" W20-50	48" 48" ROAD WORK AHEAD
7	X	×		W4-2(I		48 " W20-1
		в	L L		×	X
			∇			
						I II
F	_	L/:	2			

MINIMUM TAPER LENGTH = L (feet)										
LANE WIDTH										
(feet)	25	30	35	40	45	50	55	60	65	70
10	105	150	205	270	450	500	550	_	_	_
11	115	165	225	295	495	550	605	660	_	_
12	125	180	245	320	540	600	660	720	_	_