

To all prospective bidders:

You are being sent this Clarification for the supply of the “Panther Lake Trail Footbridge” for the City of Federal Way Parks Department. The following questions have been asked and answers in red:

1. The drawings only detail the vertical pickets on one side of the bridge and rub rail on the other. Is that intent of the project or is the intent to have the vertical pickets on both sides? **It is the intent to have vertical pickets on both sides.**
2. The plans or specification do not call out a material for the rub rail, is a rub rail required? **A rub rail is not required.**
3. The plans call for the bridge to be designed per IBC 2015 and the specs call for the bridge to be designed per the AASHTO LFRD Guide Specifications for Design of Pedestrian Bridges. Can you please confirm the required design criteria and design loading? **Design the bridge per the structural drawings, IBC 2015.**
4. The specs call for a minimum rail height of 42”, which is consistent with IBC, however the minimum railing height per AASHTO is 48”, please confirm the minimum rail height. **Minimum rail height is 42”**

Out for bids date: 4/3/2018

Bid due date: 4/24/2018, 2:00 PM

Deliver or mail by the 24th to; City Hall 33325 8th Ave S. Federal Way, WA 98003-6325 or email quotes to: [Robyn.Buck@cityoffederalway.com](mailto:Robyn.Buck@cityoffederalway.com)

If you have any question contact:



*Stephen Ikerd*

Parks Deputy Director  
Certified Arborist PN-1942A  
33325 8<sup>th</sup> Ave S. FW, WA 98003  
253 835-6911